

4-060487

12-30

15-065-01370-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 4-22-46

NW SW NE /4 SEC. 14, 09 S, 21 W  
3630 feet from S section line  
2310 feet from E section line

Operator license# 3300

Lease Balthazor well # 3

Operator: Lloyd Drilling Company

County Graham

Address: St. Peter Route  
Box 59  
Morland, Kansas 67650

Well total depth 3750 feet <sup>121.88</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 1686 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 9:00A.M. Day: 30 Month: December Year: 93

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 225 sxs. 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 3:15P.M., Day: 30, Month: December, Year: 93

Actual plugging report: 8 5/8" to 1686'. 5 1/2" to 3730'. Sand to  
3680' & spot 5 sxs. cmt. Shot casing at 1720'. Mix 12 sxs. gel followed  
by 50 sxs. cement with 100#. Pull casing to 950' and pump 75 sxs.  
cement. Pull casing to 475' and circulate cement with 40 sxs. Pull  
casing and top with 15 sxs. cement.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD     Any plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation: 2221

I did[ X ] or not[     ] observe the plugging.

**INVOICED**

DATE 1-13-94  
INV. NO. 39719

RECEIVED STATE CORPORATION COMMISSION  
RECEIVED STATE CORPORATION COMMISSION  
JAN 10 1994  
Form CP-2/3  
Wichita, Kansas  
CONSERVATION DIVISION  
Wichita, Kansas  
(agent) DH