

4-070158

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-21,441-0000

SW NE SW /4 SEC. 14, 09 S, 21 W
1650 feet from S section line
3630 feet from E section line

Operator license# 31566
Operator: Benchmark Oil & Gas

12/22

Lease: Knipp Well # 19
County: Graham \$ 130,13

Address: 1515 Arapahoe St - #580
Denver, CO 80202

Well total depth 4004 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 267 feet
W/250 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Benchmark Oil & Gas License# 31566

Address: 1515 Arapahoe St - #580 - Denver, CO 80202

Company to plug at: Hour: 2:00 P.M. Day: 22 Month: December Year: 1999

Plugging proposal received from: Rowland Nyp

Company: Benchmark Oil & Gas Phone: 785-635-0860

Were: 5 1/2" set at 3848' w/200 sxs. D.V. Tool at 1726' w/400 sxs.
Prod. Perfs 3724' - 3766'. PBDT 3752'. Fluid level 700' from surface.
Ordered out 350 sxs 60/40 pozmix 10% gel with 500# hulls.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part , None

Completed: Hour: 4:30 P.M. Day: 22, Month: December, Year: 1999

Actual plugging report: Chito's Well Service ran 66 joints 2 7/8" tubing to 2024'.
Allied pumped 75 sxs 60/40 pozmix - 10% gel with 200# hulls. Pulled tubing to 1814'. Allied
pumped 65 sxs with 300# hulls. Cement circulated. PTOH. Squeezed 100 sxs. Max. P.S.I.
900#. S.I.P. 400#.
Checked backside. Pressured to 600#. Note: D.V. Tool cwc to surface.

INVOICED

DATE 1/10/00

Remarks: WV. NO. 061084

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2230 GL

I did / did not observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION

Richard Williams
(agent)

Form CP-2/3

JAN 04 2000
1/4/00
CONSERVATION DIVISION
Wichita, Kansas

(Handwritten signature)