

10-29 15-065-01412-00-002 632

To: **6 041237**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
NW, SEC. 15, T 9 S, R 21 W/E
4620 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5629
Operator: Phillips Pet. Co. Inc.
Name & Address 701 E 10th
Great Bend, Ks. 67530

Lease Name Trexler Well # 12
County Graham 119.92
Well Total Depth 3690 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 245 w/200

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Service License Number _____
Address Hays, Ks.

Company to plug at: Hour: 12:00 PM Day: 29 Month: October Year: 19 90

Plugging proposal received from Slim Wordell
(company name) Phillips Pet. Co. (phone) _____

were: 5 1/2 casing set at 3687 w/200 sks cement; perf at 3371 to 3564; Helés in casing 1550
surf. Aordered 300 sks 60/40 poz 8% gel w/1/4 lb f.c. Plus 200 sks common.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part xx None _____
Operations Completed: Hour: 1:45PM Day: 29 Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT R. I. H. w/tubing to clean out to 1545; R. O. O. H. w/tubing
R. I. H. w/open end tubing to 1380. Spt 200 sks common plus 40 sks poz to circ.
cement at surf. P.O.O.H. w/tubing and sq add. 35 sks cement. Max 500 lbs. S.I. 300 lbs.
Hooked up to 10 3/4 s.p. and pumped 100 sks cement.
Max 400 lbs. S.I. 200 lbs. 117/91

Remarks: _____
(If additional description is necessary, use BACK of this form.)
Observe this plugging.

INVOICED

DATE JAN 14 1991
INV. NO. 30497

Signed Dennis L. Hamel
Dennis L. Hamel (TECHNICIAN)