

12-6

109R

4-031616

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-21400-00-00

NE NE NE 1/4 SEC. 15, 09 S, 21 W
4950 feet from S section line
330 feet from E section line

Operator license# 5229 Lease Morel well # A-2

Operator: Phillips Petroleum Co. County Graham

Address: Rt. 3 Well total depth 3719 feet
Box 20A Conductor Pipe: 0 inch @ 0 feet
Great Bend, Kansas 67530 Surface pipe 10 3/4 inch @ 240 feet

120.86

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Kelso License#

Address: Chase, Kansas

Company to plug at: Hour: Day: 6 Month: December Year: 91

Plugging proposal received from: Vernon Duntz

Company: Kelso Phone:

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Allied Cement Company. Keller Water. Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: Day: 6, Month: December, Year: 91

Actual plugging report: 10 3/4" @ 240' w/200 sks. 6" @ 3691' w/200
sks. Plugged bottom with sand and 6 sks. cement to 3270'. Shot pipe
4 times and recovered 0'. Pump in 6". Squeezed 6" to 1800' w/250
sx. cement blend w/500# hulls packed in. Squeezed backside w/100
sx. cement blend. Max. pressure on 6".

RECEIVED
STATE CORPORATION COMMISSION
12/16/91
DEC 16 1991

Remarks:

I did [X] / did not [] observe the plugging. Carl Goodrow

INVOICED

DATE 1-7-92

INV. NO. 34226

File S.

(agent)
Form CP-213