

5-9

6

6 020529

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-01476-60-00
SE NE SE, SEC. 18, T 9 S, R 21 W/EX

R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245
Operator: Okmar Oil Co.
Name & Address: Box 723 Hays, Ks. 67601

1650 feet from S section line
990 feet from E section line

Lease Name Sutor B Well # 3
County Graham 123.37

Well Total Depth 3796 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 157 feet 8 5/8
5 1/2 set at 3794

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Okmar Oil Co. License Number 5245

Address Same as above

Company to plug at: Hour: 9:30 Day: 9 Month: May Year: 19 90

Plugging proposal received from Bob Grant

(company name) Okmar (phone) 913-628-6101

were: Shot two holes at 1785 and at 1030. 5 1/2" set at 3794

Plugging Proposal Received by Gil Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 P Day: 9 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Pumped down tubing at 2113, 50 sks 65/35 poz 10% gel w/250 lbs. hulls. and 50 sks common cement to 1100'. Pulled tubing to 1105 and circ. cement

65/35 poz 10% gel to surface w/80 sks and 100 lbs. hulls. Pumped down annulus 25 sks and

50 lbs hulls. Shut in 100 lbs. pressure. Pump down 5 1/2" casing 70 sks 65/35 poz 10% gel and

100 lbs hulls. Max pressure 450. Shut in 250 lbs. pressure.

Remarks: By B. J. Titan (If additional description is necessary, use BACK of this form.)

I (did not observe) this plugging.

DATE MAY 22 1990

INV. NO. 28199

Signed Gilbert Balthazor (TECHNICIAN)

Stamp: MAY 16 1990 CONSERVATION DIVISION WICHITA, KANSAS