

6 031362

5-8

59

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 13-065-01441-00-00  
NE NE SE, SEC. 18, T 9 S, R 21 W/E

2310 feet from S section line  
333 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Sutor Well # B-9

Operator: Okmar Oil Co.

County Graham 123.63

Name & Address Box 723

Well Total Depth 3804 feet

Hays, Kansas 67601

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 150

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Berexco Inc. License Number Rig 2048

Address Hays, Ks.

Company to plug at: Hour: PM Day: 8 Month: May Year: 19 90

Plugging proposal received from Bob Grant

(company name) Okmar (phone) \_\_\_\_\_

were: 8 5/8 set at 150 cwc. 5 1/2 set at 3800. T.D. 3804. Perfs

ran tubing and scraper to bottom. Bad casing from 289 to 1143. Order 50 sks common cement. 225 sks 65/35 poz 10% gel 500# hulls. B. J. Titan Cement Co. OWS water trucks.

Working pit lined.

Plugging Proposal Received by Carl  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30PM Day: 8 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Ran open end tubing to 2113'. Mixed and

pumped 50 sks cement blend w/1 sk hulls mixed and pumped 50 sks common cement w/1 sk hulls.

Laid down 34 joints of tubing to 1013 . Mixed and pumped 80 sks cement blend w/hulls to

cir w/total 270 sks to max psi 300#. Close in psi 150# 8 5/8 annulus. .Sq. w/5 sks to max psi

500#. Close in psi 500#. (15 bbl to break circ)

Remarks: Anhy 1795. Elv 2304 KB

additional description is necessary, use BACK of this form.)

**INVOICED** observe this plugging.

MAY 22 1990

DATE \_\_\_\_\_

INV. NO. 28200

*Lib. S.*

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow

222