

1-30 15-065-01421-00-00

To: 6 041133
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 5153
NE SE SW, SEC. 18, T 9 S, R 21 W/E

TECHNICIAN'S PLUGGING REPORT

990 feet from S section line
2970 feet from E section line

Operator License # -6063 6033

Lease Name Forgy Well # 8

Operator: Murfin Drilling Co.
Name & Address: E. Hwy 24
Hill City, Ks. 67642

County Graham 125.35

Well Total Depth 3857 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 157 w/125 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Hays, Ks.

Company to plug at: Hour: 8:00 AM Day: 30 Month: Jan Year: 19 90

Plugging proposal received from John Niernberger

(company name) Murfin Drilling (phone)

were: 5 1/2" casing set at 3855' w/125 sks. Top perf at 3546'.
Perf anhy at 1825' and base dakota at 1025'. Annulus sq at various intervals.

Ordered 400 sks 65/35 poz 10% gel w/1/4# f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 Day: 30 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 370 sks cmt w/1/4# f.c. plus 5 sks hulls mixed
in cement. Max 900#. S.I. 700# psi. Pumped in 8 5/8" casing 30 sks cement w/1/4# f.c. mixed in
cement. Max 300#.

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-15-90
INV. NO. 27462
1-30

[Signature]

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel