

15-065-01417-00-00

6-13

4-041682

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15- - 8-51
SW SW SW /4 SEC. 18, 09 S, 21 W
330 feet from S section line
4950 feet from E section line

Operator license# 30606 Lease Forgy well # 4

Operator: Murfin Drilling Company, Inc. County Graham 124.64

Address: 250 N. Water Well total depth 3835 feet
suite #300 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 145 feet
w/125 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 7:00A.M. Day: 13 Month: June Year: 95

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Company, Inc. Phone:

Were: 5 1/2" casing set at 3829' w/125 sxs. cement. O.H. at 3829' - 3835'.
Anhy. at 1830' - Dakota at 1050' - W.L.M. at 3830' - T.O.F. at 1500'.
Order 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls plus 14
sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 8:15A.M., Day: 13, Month: June, Year: 95

Actual plugging report: R.U. cementers squeezed 5 1/2" casing. 25 sxs.
cement with 200# hulls, followed with 14 sxs. gel, followed with 200 sxs.
cement with 200# hulls. Max. P.S.I. 750#. S.I.P. 300#.
Hooked-up to 8 5/8" S.P. Squeezed 50 sxs. cement with 100# hulls.
Max. P.S.I. 100#. S.I.P. 50#.

STATE CORPORATION COMMISSION
RECEIVED
JUN 21 1995
6-21-95

Remarks:
Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES X, CALC X, NO Dakota plug:YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging. Dennis L. Hamel
(agent)

INVOICED

DATE 6-23-95
INV. NO. 42988