

6-13 15-065-01426-00-00

4-041684

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

API number: 15- - 12-56  
S2 NE NW /4 SEC. 18, 09 S, 21 W  
4290 feet from S section line  
3300 feet from E section line

Operator license# 30606 Lease Forgy well # 13

Operator: Murfin Drilling Company, Inc. County Graham 124.54

Address: 250 N. Water Well total depth 3832 feet  
Suite #300 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 174 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 13 Month: June Year: 95

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Company, Inc. Phone: \_\_\_\_\_

Were: 5 1/2" casing set at 3830' w/125 sxs. cement. O.H. at 3830' - 3836'.  
Anhy. at 1830' - Dakota at 1050' - Perf. casing at 265'.  
Order 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:00P.M., Day: 13, Month: June, Year: 95

Actual plugging report: R.I.H. with tubing to 2356'. Spotted 185 sxs. cement  
with 200# hulls to circulate cement at surface. P.O.O.H. with tubing.  
Hooked-up to 8 5/8" S.P. Pressured-up to 1000#. R.U. perforators - perf.  
casing at 265'. Hooked-up cementers to 5 1/2" casing. Squeezed casing with  
75 sxs. cement. Max. P.S.I. 300#. S.I.P. 100#. Hooked back up to 8 5/8"  
S.P. Pressured-up again to 1000#. Job complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy. plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES  , CALC  , NO \_\_\_\_\_ Dakota plug: YES  , NO \_\_\_\_\_  
Plugged through TUBING  , CASING \_\_\_\_\_ . Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging. Dennis L. Hamel  
(agent)

STATE CORPORATION COMMISSION  
6-21-95  
JUN 21 1995

**INVOICED**  
DATE 6-23-95  
INV. NO. 42990