

4-041685

6-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15-065-21,528 -00-00
SW SE SW /4 SEC. 18, 09 S, 21 W
330 feet from S section line
3630 feet from E section line

Operator license# 30606 Lease Forgy well # 14

Operator: Murfin Drilling Company, Inc. County Graham 128.05

Address: 250 N. Water Well total depth 3940 feet
Suite #300 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 176 feet
w/150 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 13 Month: June Year: 95

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Company, Inc. Phone:

Were: 5 1/2" casing set at 3839' w/100 sxs. cement. Perf. at 3842' - 3845'.
Port collar at 1873' cemented with 300 sxs. T.O.C. at 500' as per bond log.
Perforated casing at 300'.
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls plus
14 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 2:00P.M., Day: 13, Month: June, Year: 95

Actual plugging report: Pumped down casing with 25 sxs cement and 200# hulls,
followed with 14 sxs. gel, followed with 125 sxs. cement with 200# hulls.
Max. P.S.I. 500#. S.I.P. 300#. 8 5/8"
S.P. - pumped down 50 sxs. cement with 100# hulls. Max. P.S.I. 200#. S.I.P.
100#.

RECEIVED
STATE CORPORATION COMMISSION

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X / did not [] observe the plugging.

Dennis L. Hamel
(agent)

JUN 21 1995
6-21-95

INVOICED
DATE 6-23-95
INV. NO. 42991