

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01427-00-00
Spot: CSESENE Sec/Twnshp/Rge: 18-9S-21W
2970 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: SEEFELD A Well Number: 1
County: GRAHAM Total Vertical Depth: 3797 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Production Casing Size: 5.5 feet: 3793 175 SX CMT
Surface Casing Size: 8.625 feet: 201 150 SX CMT

\$123.40

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2003 9:00 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 360 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perfs 3533'-3538'; 3680'- 3684'.
CIBP at 3720'.
Squeezed in 1953 - hole at 1332' w/225 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/09/2003 1:30 AM KCC Agent: PAT STAAB


Actual Plugging Report:

Berexco RIH with tubing to 3500' - pumped 125 sxs 60/40 pozmix with 400# hulls.
Tied onto backside and pumped 16 sxs with Max. P.S.I. 200#. S.I.P. 0#.
Blew cement out of bottom of head.
Pulled tubing to 1854' - pumped 120 sxs 60/40 pozmix with 200# hulls to circulate cement to surface.
Pulled tubing and tied onto casing with a swedge - pumped 20 sxs 60/40 pozmix.
Max. P.S.I. 1000#. S.I.P. 450#.

Remarks: ALLIED CEMENTING COMPANY-TICKET #12210.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-15-03

NV NO. 2003061408

APR 09 2003

CITIES SERVICE OIL CO. #1 SEEFELD 18-9-21W 22
SE SE NE

Contr. IRINE DRILLING COMPANY GRAHAM County

E. 2296 Comm. 4-22-50 Comp. 5-19-50 IP 3000 BOPD

Tops	Depth	Datum	Casing
			8" 201 1600' OIL/ 45 MIN
			5" 3793 PMP 106 BO/10 HRS:
LANS	3494	-1198	
ARB	3791	-1495	
T.D.	3797	-1501	

MOREL WEST

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS