

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01428-00-00  
Spot: CNW,SENE, Sec/Twnshp/Rge: 18-9S-21W  
3630 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: SEEFELD Well Number: 2  
County: GRAHAM Total Vertical Depth: 3793 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/23.27  
Surface Casing: Size 8.625 feet: 240 w/150 sxs cmt  
Production: Size 5.5 feet: 3780 w/175 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/18/2002 8:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Revd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 340 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Casing bad from 1086' - 2925'.  
CIBP at 3760'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/18/2002 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 2700'.  
Tied onto tubing - mixed and circulated cement with 240 sxs and 800# hulls.  
POOH. Topped 5 1/2" with 70 sxs cement - circulating up 8 5/8".

RECEIVED  
JUN 24 2002  
6-24-02  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer  
(TECHNICIAN)

INVOICED

DATE 6-24-02  
TEL. NO. 2002062007

Form CP-2/3

JUN 20 2002


CITIES SERVICE OIL CO. #2 SEEFELD 18-9-21W 22  
 NW SE NE

Contr. \_\_\_\_\_ GRAHAM County

E 2277 Comm. 5-11-50 Comp. 6-9-50 IP 1620 BOPD  
 DRAW DOWN

Tops	Depth	Datum	Casing
ANK		+522	
HEEB	311.7	-1170	8" 240 5" 3780
LANS	3486	-1209	
CONG	3754	-1477	
SIMP SH	3774	-1497	
ARB	3778	-1507	
T.D.	3793	-1516	

MOREL POOL



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS