

To: 6 070801
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

Nov 1950

SE NW NE, SEC. 18, T 9 S, R 21 W XX

4290 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Seefeld Well # A 4 SWD

Operator: Berexco Inc.
Name &

County Graham 139.46

Address Box 723

Well Total Depth 4291 feet

Hays, Ks. 67601

Conductor Pipe: Size 0 feet

Ted Crawford

Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan and Company Tools License Number

Address 1707 East 10 St. and East 8th Street Hays, Ks. 67601

Company to plug at: Hour: PM Day: 9 Month: Nov Year: 19 89

Plugging proposal received from George Jorgenson Ted Crawford

(company name) Berexco Inc. (phone) 628-6101

were: 8 5/8" - 238' S.P. cwc w/175 sks cement. 5 1/2" casing at 3791' w/175 sks cement.

D. V. tool at 1804' cwc w/550 sks cement. Open hole 3791' to 4291'. Also squeezed with

palmer injectioral and drilled out 3851' to 2974'. Proposal by Don Butcher 100 sks Class A

common 2% gel and 500 sks 65/35 poz 6% gel 3% cal cl and 5 sks hulls. Spot with tubing, load
both 5 1/2" casing and annulus with cement. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:00 PM Day: 9 Month: Nov Year: 19 89

ACTUAL PLUGGING REPORT Berexco ordered 100 sks Class A Common 2% gel and 500 sks 65/35 poz

3% cal cl and 5 sks hulls. Spotted through tubing. 1. 2 7/8" tubing at 2802' w/100 sks

common cement. 2. 2 7/8" tubing at 1818' pumped in 300 sks cement w/2 sks hulls. 3. 2 3/8"

tubing at 920' w/100 sks cmeent, cement circulated 4. Squeezed 5 1/2" casing w/100 sks cement.

5. Pressured annulus with cement, did not take cement pressure, 800 psig. Max

Remarks: Cemented by B. J. Titan

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

DATE 12-13-89

INV. NO. 26787

Signed Marion J. Schmidt
(TECHNICIAN)

Marion J. Schmidt

FORM CP-2/3
Rev. 01-84

RECEIVED
CONSERVATION COMMISSION
12-13-89
DEC 13 1989
WICHITA, KANSAS