

4-041648

12-14

D-16,549

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 10-13-56

S2 NE SW /4 SEC. 18 , 09 S, 21 W
1650 feet from S section line
1980 3300 feet from E section line

Operator license# 30606

Lease Forgy well # 12

Operator: Murfin Drilling Company

County Graham

Address: 250 N. Water
Suite #300
Wichita, Kansas 67202

Well total depth 4080 feet ^{132.60}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 164 feet
w/125 sxs.

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00A.M Day: 14 Month: December Year: 94

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Company Phone:

Were: 5 1/2" casing set @ 3856' w/100 sxs. cmt. Perf. @ 3856' - 4080'.
Anhy. @ 1825'. Bad casing and fish in hole - casing squeezed prior to
plug. Ordered 100 sxs. common with 1/4# F.C. plus 200 sxs. 60/40 pozmix
6% gel with 1/4# F.C.

Note: 5 1/2" casing perf. @ 1578' & cmt'd w/ 675 sxs cmt. - also enclosed
operator workover & plug report. DN

Plugging Proposal Received by: Dennis Hamel - Don Butcher
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:30P.M., Day: 14, Month: December, Year: 94

Actual plugging report: Perf. casing at 194'. Ran tubing to 204'.
Spotted 100 sxs. common and 60 sxs. 60/40 pozmix - 6% gel to circulate
cement at surface. Pulled tubing and pumped additional 100 sxs. cement
down casing with cement coming to surface in annulus. Shut in annulus
and squeezed casing with additional 40 sxs. cement. Max. P.S.I. 300#.

STATE CORPORATION COMMISSION

FEB 0 8 1995
2-6-95

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did X / did not] observe the plugging.

Dennis Hamel

INVOICED
DATE 2-7-95
INV. NO. 42173

OK
Butcher (agent)