

6 031083

4-27-88 15-065-03424-00-00

API NUMBER 15- 1953

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SW SW, SEC. 32, T 9 S, R 21 (W/E)

330 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5163

Lease Name Denning Well # 3

Operator: White Hawk Oil Co.  
Name & Address: Box 1150  
Great Bend, Ks. 67530

County Graham 126.85

Well Total Depth 3903 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 170

Abandoned Oil Well X Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co License Number

Address Ness City, Ks.

Company to plug at: Hour: Day: 27 Month: April Year: 19 88

Plugging proposal received from Bob Lundberg

(company name) White Hawk (phone)

were: 8 5/8" set at 170' w/150 sks cwc. 5 1/2" set at 3626' w/110 sks. PBSD

3626'. Perf 3565' - 88'. Shots in Anhy at 1780' and below Dakota at 1000'.

Order 300 sks ATL Cement Blend 5 sks Hulls Allied Cement Co. OWS Water Trucks.

Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:15AM Day: 27 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" csg w/200 sks cement w/4 sks Hulls in last

100 sks cement to Max Psi 800'. Close in Psi 300#. Squeezed 8 5/8" w/100 sks cement w/1 sk

Hulls to max Psi 300#. Close in Psi 150#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

5/17/88

MAY 17 1988

CONSERVATION DIVISION  
Wichita, Kansas

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED (If applicable) observe this plugging.

DATE 5-19-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 20788