

15-065-00183-00-00 *R*

6030504

API NUMBER 15- 6-7-50

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NWSE54 SEC. 32, T. 9 S, R. 21 W

N 990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5163

Lease Name Denning Well # 2

Operator: White Hawk Oil Co.

County Graham 125.36

Name & Address P.O. Box 1140

Well Total Depth 3857' feet

Great Bend, Kansas
67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement Co. License Number _____

Address Hays Kansas

Company to plug at: Hour: AM Day: 9 Month: 7 Year: 19 85

Plugging proposal received from Bob Lundberg

(company name) White Hawk Oil Co. (phone) _____

were: 9 5/8 act @ 208 w/ 150 sy 5 1/2 act @ 3850 w/ 115 sy.

CIBP set above Top Perf. @ 3490 well had been squeezed at 1226

and had black magic behind 5 1/2". Ordered 200 sy

5040 sy 60 gel 3% cc 25 sy gel 4 ax huller - Work over Rig

and work string of tubing. Dresher water truck.

Halliburton Cement. Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 9 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT Rig up and run tubing - tag bottom @ 3490
tie on to back side try to pump instant pressure stop at
700# didn't break down closed in. Hook up to tubing displace 50
sy cement mix. lay down pipe to 2880 displace 134 gel.
lay down pipe to 1750 displace 140 sy cement mix to surface
lay down pipe load hole and squeeze with 10 sy cement mix.

Remarks: Max 700# release and fluid held at surface. Plug complete.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-26-85

INV. NO. 9145 7-9

STATE CORPORATION COMMISSION
FRI JUL 19 1985
CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow
(TECHNICIAN) *16*