

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21466-00-01

Spot: CSWSWSE

Sec/Twnshp/Rge: 32-9S-21W

330 feet from S Section Line, 2310 feet from E Section Line

Lease/Unit Name: WIDENER

Well Number: 1

County: GRAHAM

Total Vertical Depth: 3860 feet

Operator License No.: 31274

Conductor Pipe: Size

feet:

Op Name: HRBEK, R.L.

Surface Casing: Size 10.75

feet: 280

w/200 sxs cmt

Address: RR 1, BOX 11

Production: Size 5.5

feet: 3858

w/175 sxs cmt

MERINO, CO 80741

Liner: Size

feet:

705.12

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/18/2001 8:00 AM

Plug Co. License No.: 31664

Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM

Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed
Plugging
Method:

Order 12 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/18/2001 10:00 AM

KCC Agent: CARL GOODROW

Actual Plugging Report:

10 3/4" set at 280' w/200 sxs cwc.

5 1/2" set at 3858' w/175 sxs.

ARB. OH 3856' - 3860'.

Filled 5 1/2" w/12 yards Redi-Mix.

INVOICED

DATE 5-01-01
INV. NO. 2001061742

RECEIVED

KANSAS CORPORATION COMMISSION

MAY 1 2001

CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

APR 25 2001

replacement card

F & J OIL CO
EL DORADO KS

32-09S-21W
SW SW SE

#1 WIDENER OWWO

site: 1-3/4 S & 6-1/4 W OF PALCO KS

city: GRAHAM

API 15-065-21466-A

contr: POE WELL SVC

field: COOPER

well:

fr date 08/11/81

spd date 02/04/82

drilg comp 02/05/82

card issued 04/22/82

last revised 02/16/98

ELV: 2302 KB, 2297 GL SMP
tops.....depth/datum
SC.....1770 + 532
TOP.....3275 - 973
HEEB.....3480 - 1178
LEAV.....3484 - 1182
DODGE.....3502 - 1200
LANS.....3520 - 1218
BKC.....3748 - 1446
CONG.....3810 - 1508
SIMP.....3848 - 1546
ARB.....3856 - 1554
RTD OLD.....3860 - 1558

IP status:

OIL, P 6 BOPD, LKC, INTV NA, 04/15/82
CORR & INFO REL: 2/16/98 - CORR TOP (WAS TOP 3223); ADDED DSTS; CORR WO DATE
NOTE: CORR 8/18/81 - ORIG FR AS NEW WELL; ADDED OLD INFO
OLD INFO: OPERATOR WAS DEEP ROCK OIL CORP, 1 EARLY, SPD 06/07/50, 06/22/50 10-3/4" 280 / 200 SX, 5-1/2" 3858.5 / 175 SX, OIL, P 135 BO & 2.8 BWPD, ARB 3859-3860, 06/25/50 (CARD ISSUED 08/25/50)
CONTR: RINE DRILLING

F & J OIL CO
EL DORADO KS

32-09S-21W
SW SW SE

#1 WIDENER OWWO

DRLR SD ZNS: 1560-1770 (MSTLY SH, W/SD), 3000-3138 (MSTLY SH, W/SD)
SHOWS: 3330-3338 (TOP LM, SLI PORO, FR STN), 3448-3455 (SHAW LM, PNPT PORO, FSFHO, NO ODOR), 3504-3512 (DODGE LM, SME PORO, POSS TR STN), 3558-3563 (LANS LM, FR VUG PORO, ODOR, SME FO, LT STN IN DRY SMPL), 3604-3612 (LANS LM, FR PNPT PORO, FR ODOR, SFO, GD STN, SME DEAD OIL), 3616-3642 (LANS LM, POSS PORO STRK, STN), 3716-3720 (LANS LM, SME PNPT PORO, NO ODOR, FR STN, SLI TR FO), 3856-3860 (ARB DOL, FR PORO, SFO, POSS TR ODOR)
NO CORES
DST (1) 3447-3456 (SHAW), / OP 40", SLI BLO & DIED/20", REC 30' SLI OCM, NW, FP NA ISIP 860#
DST (2) 3457-3473 (SHAW), / OP 40", REC 20' SLI OCM, NW, FP NA ISIP 620#
DST (3) 3553-3570 (LKC), / OP 30", VGB, GTS/40", REC 1290' CLEAN OIL, 180' OILY M & MDY OIL, NW ISIP 900# IFP 370#
DST (4) 3708-3725 (LKC), / OP 30", SLI BLO, PKR WSHD OUT, REC ALL DM, RECONDITIONED HOLE
DST (5) 3711-3725 (LKC), PKR WOULD NOT HOLD, MISRUN
MICT - CO, (ARB OH), FU 1200' OIL, NW/4 HRS, FU 2250' OIL, NW/10 HRS, SWB 1000' OFF BTM, SWB 72 BO/4 HRS, NAT, SWB 8 BOPH/3 HRS, POP, IPP 135 BOPD & 2% W, 6/25/50
NEW INFO: FR 08/11/81, RE-ENTERED 02/04/82 WSH DWN DC 02/05/82 CSG: PROD CSG ALREADY IN HOLE MICT - CO, PF (LKC) INTV NA, AC'D, SO, POP, IPP 6 BOPD 4/15/82 - NO OTHER INFO RELEASED BY OPERATOR OR ON KCC RECORDS; ALL REQUESTS FOR INFO DENIED