

15-163-03824-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER Completed 06/22/50 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Phillips Petroleum Company OPERATORS LICENSE NO. 5229

ADDRESS Route 3, Box 20-A, Great Bend, Kansas 67530 PHONE # (316) 793-8421

LEASE (FARM) Nettie Unit WELL NO. D02 WELL LOCATION SW SW SE COUNTY Rooks

SEC. 34 TWP. 9S RGE. 17 (E) or (W) TOTAL DEPTH 4049 PLUG BACK TD 4049

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. C-3373
44,977-C

SURFACE CASING SIZE 8 5/8 SET AT 168' CEMENTED WITH 100 SACKS

CASING SIZE 5 1/2 SET AT 3462' CEMENTED WITH 100 SACKS

Liner Size 4 1/2 Set At 3434-3550'. Cemented with 125 sacks

PERFORATED AT Open Hole: 3550-4049'

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK X JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL See attached procedure

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

A. M. Wardell

PHONE # (913) 434-4638

ADDRESS 510 NW Third Street, Plainville, Kansas 67663

PLUGGING CONTRACTOR Phillips Petroleum Company

LICENSE NO. 5229

ADDRESS 510 NW Third Street, Plainville, Kansas 67663

PHONE # (913) 434-4638

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: _____

J. W. Taylor
(Operator or Agent)

DATE: 1/2/90

(4)

JAN 8 1990
1-8-90
CONSERVATION DIVISION
Wichita, Kansas

Date: January 4, 1990
 Number: 00000011

P&A Procedure for Nettie Unit #D-02

Nettie Unit No. D-02
 SW SW SW Sec. 34-T9S-R17W
 Rooks County, Kansas
 Nettie Field, Arbuckle Formation

Procedure # 175-89
 Charge Code 80-7159
 Lease Code 350125
 W.I. 31.65017 %
 R.I. 27.52178 %

Elevation: 2043' DF

Casings: 8 5/8" set @ 168' w/ 100 sx cement.

5 1/2" set @ 3462' w/ 100 sx cement.

Liner: 4 1/2" set @ 3434' - 3550' w/ 125 sx cement.

Open Hole: 3550' - 4049'

Note: LKC Perforations (3193' - 3417' OA) squeezed off w/ 650 sx cement in 1953. Casing leaks in Anhydrite at 1300' and Dakota squeezed off w/ 565 sx cement in 1953. Last MIT 1984. Has developed leaks. Decision to P&A instead of repair.

Objective: Plug and Abandon shut down SWD well by running tubing to 1400' filling hole with 65/35 pozmix-10% gel. (per Carl Goodrow)

Procedure:

1. Notify KCC representative 24 hours prior to beginning plugging operations (Hays office 628-1200).
2. Move in and rig up Well Service Unit and Cementing Company. Go in hole with work string tubing to 1400' to get below anhydrite. Pump 270 sx of 65/35 pozmix-10% gel and hulls to fill hole below 1400'. Lay down work string tubing. Swedge in 5 1/2" casing and pump 250-300 sx cement & 6 sx hulls. Shut in under pressure. (Total volume inside 5 1/2" calculated at 119 bbls with 20% excess, at 3.5 sx/bbl pozmix yield gives ~416 sx of 65/35 pozmix-10% gel to fill casing).
 Water requirement for 500 sx cement @ 3.5 sx/bbl = 142 bbls fresh water.
3. Rig up to 5 1/2" - 8 5/8" annulus and pump into, if possible, with 50 sx cement and shut in under pressure.
4. Check fillup in casings and outside of 8 5/8" csg. If necessary, fill to surface w/ redimix.
5. Cut off casing 3' below ground level and weld on steel plate marked with "PPCo, well name, and date plugged."
6. Restore location.

STANDARD OIL COMPANY

JAN 8 1990

DEPARTMENT OF PETROLEUM
 OPERATIONS

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE

APR 10 1990

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

January 10, 1990
**NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION**

Phillips Petroleum Company
Route 3, Box 20-A
Great Bend, KS 67530

Nettie Unit DO 2
SW SW SE
Sec. 34-09-17W
Rooks County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Director

District: #4 2301 E. 13th

Hays, KS 67601.

(913) 628-1200