

6 030731

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5/2 NE NE, SEC. 26, T. 9 S., R. 19 (W)

4290 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name BENOTT Well # B 1

Operator: JOHN O FARMER

County ROOKS 116.16

Name & Address BOX 352

Well Total Depth 3574 feet

RUSSELL KANSAS

Conductor Pipe: Size _____ feet

67665

Surface Casing: Size 8 5/8 feet 206'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON License Number _____

Address HAYS KANSAS

Company to plug at: Hour: PM Day: 30 Month: 4 Year: 19 86

Plugging proposal received from SHIM REICHMAN

(company name) JOHN O FARMER (phone) _____

were: 8 5/8 @ 206' w/150sx. 5 1/2" @ 3572' w/100sx. PERF 3308'-3574'

ORDER SAND & com. CMT. SHOOT & PULL PIPE ORDER 180sx.

60/40p02 6% GEL 3% cc 5sx. HULLS HALLIBURTON CMT. CO.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45PM Day: 30 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT SAND TO 3250' SPOT 5SX. COM CMT ON SAND w/BOILER

RECOVERED 1250' 5 1/2". TIE ON TO 8 5/8 MIX & PUMP 4SX. HULLS

35 SX. GEL. 100SX. CMT. MIX + 1SX HULLS 5SX. GEL 80SX. CMT MIX.

MAX. PSI 700th CLOSE IN 150th PLUG COMP.

STATE CORPORATION COMMISSION

MAY 16 1986

5/16/86
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

(If did/did not) observe this plugging.

DATE MAY 16 1986

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 13861