

9-3

1192

6-060249

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-23,179 -00-00
90'N. of
SE SW NW /4 SEC. 26, 9 S, 19 W
3060 feet from S section line
4290 feet from E section line

Operator license# 5063

Lease Pywell well # 1

Operator: Energy Exploration Inc.

County Rooks 120.25

Address: 1002 S. Broadway
Wichita, Kansas 67211

Well total depth 3700 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 214 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Abercrombie Drilling, Inc. License# 5422

Address: Wichita, Kansas 67202

Company to plug at: Hour: 8:45P.M. Day: 3 Month: September Year: 91

Plugging proposal received from: Harold Maley

Company: Abercrombie Drilling, Inc. phone: _____

Were: Order 215 sxs. 60/40 pos. - 6% Gel. - 1/4# flocel per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour: 8:45P.M., Day: 3, Month: September, Year: 91

Actual plugging report:
1st plug at 3620' with 25 sxs. - Arbuckle 3645'.
2nd plug at 1550' with 25 sxs. - Anhydrite 1536' - 1592'.
3rd plug at 925' with 100 sxs. - Dakota 621' - 921'.
4th plug at 265' with 40 sxs. - Surface pipe to 214'.
5th plug at 40' with 10 sxs.
Rathole with 15 sxs.

Remarks: Allied Cementing. 10/2/91

I did observe the plugging.

INVOICED

DATE 10-4-91

INV. NO. 33260

Herb S.

(agent)
Form CP-2/3