

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01677-00-00  
Spot: CNESWNE Sec/Twnshp/Rge: 23-9S-19W  
3630 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: CERROW Well Number: 2  
County: ROOKS Total Vertical Depth: 3531 feet

Operator License No.: 31430  
Op Name: WHITE EAGLE RESOURCES CORP.  
Address: 881 W. CHESTNUT CIRCLE  
LOUISVILLE, CO 80027

Conductor Pipe: Size feet: \$114.76  
Surface Casing: Size 13 feet: 152 200 SX CMT  
Production: Size 5 feet: 3526 200 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/29/2002 11:00 AM

Plug Co. License No.: 31430 Plug Co. Name: WHITE EAGLE RESOURCES CORP.

Proposal Rcvd. from: RANDY WEIGEL Company: WHITE EAGLE RESOURCES CORP. Phone: (785) 434-4900

Proposed Plugging Method: Shot casing at 875' - 1525' - 1975' prior to plugging.  
Ordered 350 sxs 60/40 pozmix - 10% gel plus 500# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/29/2002 1:00 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 2000'.  
Spotted 250 sxs cement with 400# hulls mixed in cement to circulate to surface.  
POOH with tubing - tied onto production casing and squeezed with 60 sxs cement with 50# hulls mixed in cement to Max. P.S.I. 400#.  
Tied onto 13" S.P. and squeezed 15 sxs cement with 50# hulls in annulus to Max. P.S.I. 300#.  
Job complete.

RECEIVED  
2/5/02  
FEB - 5 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

HD

INVOICED

Form CP-2/3

DATE Feb 6-02

INV. NO. 2002061343

FEB 04 2002

1E-04

STANOLIND OIL & GAS CO #2 CERROW 23-9-19W  
 NE SW NE  
 Contr. \_\_\_\_\_ ROOKS \_\_\_\_\_ County  
 E 2105 Comm. 9-11-48 Comp. 10-15-48 IP 1720 BOPD ECHO

Tops	Depth	Datum	Casing
ANH	1492	+613	13" 152 5" 3526
TOP	3043	-938	
LANS	3285	-1180	
ARB	3524	-1419	
T.D.	3531	-1426	


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS