

15-163-01668-00-00

4-041801

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

9-24

API Number: 15- - 7-54

NE NE SW /4 SEC. 19, 09 S, 19 W
2310 feet from S section line
2970 feet from E section line

Operator license# 30606

Lease: Boucher Well # A-2

Operator: Murfin Drilling Company, Inc.

County: Rooks 117.84

Address: 250 N. Water
Suite #300
Wichita, Kansas 67202

Well total depth 3626 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 186 feet
w/150 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day 24 Month: September Year 1996

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Company, Inc. Phone:

Were: 5 1/2" casing set at 3626' w/250 sxs cement. Perf. at 3576' - 3582'. Salt at 2200'
Anhy. at 1570' - Dakota at 950' - W.L.M. at 3600'.
Ordered 275 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - 14 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 10:30 A.M., Day 24, Month: September, Year: 1996

Actual plugging report: R.U. Perf. shot casing at 2200' - 1570' - 950'. R.U. Cementers to 5 1/2" casing to squeeze as follows: 25 sxs cement with 200# hulls and 14 sxs gel - 200 sxs cement with 200# hulls. Max. P.S.I. 800#. S.I.P. 700#. R.U. Cementers to 8 5/8" S.P. Pressured-up to 800#.

Remarks:

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC X, NO
Plugged through TUBING, CASING X
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 10-10-96

INV. NO. 46679

10/9/96

100