

6 070827

X. 2-8

F  
20,604  
00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION E/2 E/2 SE, SEC. 19, T 9 S, R 19 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-21,231

E/2 E/2 SE, SEC. 19, T 9 S, R 19 W/E

1320 feet from S section line

330 feet from E section line

Lease Name Marcotte Well # 3 SWD

County Rooks 122.72

Well Total Depth 3776 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 312

Operator License # 6484

Operator: Anderson Energy

Name & Address 200 East First St. #414

Wichita, Ks. 67202

William Anderson

Abandoned Oil Well Gas Well Input Well X SWD Well 3 D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Express Well Service License Number

Address Plainville, Ks. and Victoria, Ks.

Company to plug at: Hour: AM Day: 8th Month: Feb Year: 19 90

Plugging proposal received from Bob Wahlmeier Don Butcher KCC

(company name) Agent for Anderson Energy (phone) 316-265-7929

were: 8 5/8" - 312' s.p. cwc w/200 sks cement. 5 1/2" casing set at 3562' w/150 sks cement. 5 1/2" casing squeezed from 1550' to surface w/375 sks cement; 5 1/2" casing also squeeze at 1550' and 800' and 1800' w/1000 sks cement. Total (casing leak) Proposal 500 sks 65/35

poz 6% gel and 5' sks hulls. Run tubing to a minimum of 2200'. Spot cement through tubing. Circulate cement from bottom to top. Shut in under pressure. Load 5 1/2" and 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 2:45PM Day: 8 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT Anderson ordered 500 sks 65/35 poz 6% gel and 5 sks hulls also.

and 200 sks 65/35 poz 6% gel. Pumped in with pump truck spotted cement through tubing and displaced (1) 2 3/8" tubing at 2211'. Spotted 310 sks cement. (2) 2 2/8" tubing at 1600' w/100 sks cement w/4 sks hulls. (3) 2 3/8" at 800'. Spotted another 235 sks w/4 sks hulls. Cement circulated out of 5 1/2" casing. (4) Annulus w/5 sks cement. Max pressure 400 psig.

Shut in at 250 psig. (5) Squeezed 5 1/2" casing w/50 sks cement. Max pressure 200 psig. Shut in at 100 psig.

Remarks: Cemented by Allied Cementing Plainville. (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

3/11/90

DATE MAR 13 1990

INV. NO. 27612

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt