

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03050-00-00
Spot: CS2SWSW Sec/Twnshp/Rge: 24-9S-19W
330 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: JELINEK Well Number: 5
County: ROOKS Total Vertical Depth: 3661 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Conductor Pipe: Size feet: \$118.98
Surface Casing: Size 8.625 feet: 286 200 SX CMT
Production: Size 4.5 feet: 3640 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/25/2002 9:30 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-7202

Proposed Ar buckle open hole completion from 3640' - 3661'.
Plugging Bad casing from 1300' - 1528'.
Method: Anhydrite 1560'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/25/2002 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1395' - unable to get back to 1528' - hole sluffed.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 500# hulls - cement circulated.
PTOH. Allied squeezed down 4 1/2" casing with 150 sxs.
Max. P.S.I. 200#. S.I.P. 0#.
March 4, 2002 - Cement fell back 200' from surface. Topped off with 50 sxs to surface.

RECEIVED
3/11/02
MAR 11 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams
(TECHNICIAN)

INVOICED

DATE Mar 12-02

INV. NO. 2002061516

Form CP-2/3

MAR 08 2002

DERBY OIL ET AL #5 JELINEK Arb 22 24-9-19W
S2 SW SW

Contr. GLENN PEEL DRILLING CO. ROOKS County

E 2169 Comm. 3-10-49 Comp. 5-8-49 IP 58 BOPD PHY POT

Tops	Depth	Datum	Casing
Arb	1560		
			8" 285 PERF 15 S, 3000-
			5" 3640 05: ACID 500: SWB
HEEB	3314	- 1145	40 BO & 75 BW/4
			HRS: PERF 23 S, 3508-
LANS	3347	- 1178	95: SWB 1/2 BOFH/
			6 HRS: SWB 60 BO
			& 65 BW/5 HRS: SQZ:
ARB	3586	- 1417	PERF 24 S, 3591-
			96: ACID 800
T.D.	3641	- 1472	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS