

9-20

6 040948

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-21,215 -00-00
NE NE, SEC. 24, T 9 S, R 19 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050
Operator: Kelso Casing Pulling Inc.
Name & Address: Box 347, Chase, Ks. 67524

feet from S section line
feet from E section line
Lease Name Mahew Well # 2
County Rooks 118.59
Well Total Depth 3649 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 177'w/110 sks

Abandoned Oil Well x Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number
Address Plainville, Ks.

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Ronnie Hoover
(company name) Kelso Casing (phone)

were: 4" casing set at 3648' w/150 sks. Top perf at 3612' - 22'. P.B. Sand to 3560' and dumped 4 sks cement on sand. Shot at 2840' and 2425' and rec same. Ordered 300 sks 60/40 Poz 8% Gel w/1/2# F.C. plus 8 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 2:00 Day: 20 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Spotted 50 sks cement at 1600'; displaced cement w/8 sks Gel; Pulled to 900'; spotted 100 sks cement; displaced w/3 sks gel; pulled to 250' Spotted 40 sks cement; pulled remainder of casing; filled to surface w/10 sks. Plugged thru casing

RECEIVED STATE CORPORATION COMMISSION 12/29/88

Remarks: (If additional description is necessary, use BACK of this report) I did not observe this plugging.

INVOICED

Signed Dennis L. Hamel (TECHNICIAN)

DATE 1-5-89 INV. NO. 23488 9-20

JAN 06 1989