

7-21

4-070103

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-21,162 <sup>00-06</sup>  
100'E.of  
NE SW SE /4 SEC. 17, 09 S, 19 W  
990 feet from S section line  
1750 feet from E section line

Operator license# 31389

Lease: Whisman Well # A-1

Operator: Noble Petroleum

County: Rooks 115.64

Address: 3101 N. Rock Road - #125  
Wichita, Kansas 67226

Well total depth 3558 feet  
Conductor Pipe: 0 inch @ 0 sxs.  
Surface pipe 8 5/8 Inch @ 322 feet  
W/200 sxs.

ABAND. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD. \_\_\_\_\_, D&A \_\_\_\_\_

Plugging contractor: Noble Petroleum License# 31389

Address: 3101 N. Rock Road - #125 - Wichita, Kansas 67226

Company to plug at: Hour: 4:00 P.M. Day: 21 Month: July Year: 1998

Plugging proposal received from: Gary Sharp

Company: Noble Petroleum Phone: 316-636-2222

Were: 5 1/2" set at 3555' w/150 sxs. PBTB 3511'.  
D.V. Tool at 1500' cwc. Perfs at 3352' - 3472'.  
T.D. 3558'.  
Ordered 175 sxs 60/40 pozmix - 10% gel with 1/4 floseal - 500# hulls - 17 sxs gel.

Plugging Proposal Received by: Rich Williams  
Plugging operations attended by agent? All[  ], Part[ ], None[ ]

Completed: Hour: 5:00 P.M. Day: 21, Month: July, Year: 1998

Actual plugging report: Allied pumped 40 sxs 60/40 pozmix - 10% gel w/200# hulls, followed with 17 sxs gel, followed with 110 sxs 60/40 pozmix - 10% gel with 1/4 floseal w/200# hulls. Max. P.S.I. 1000#. S.I.P. 800#. Hooked up to annulus and pumped 1/2 bbl. Pressured up to 1000#. Released pressure on 5 1/2" casing and annulus.

Remarks:  
Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES  NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING . Elevation: 2088 GL

I did[  ] / did not[ ] observe the plugging.

*Richard Williams*  
(agent)

Form CP-2/3

**INVOICED**  
JUL 30 1998

DATE \_\_\_\_\_  
INV. NO. 51049