

8-28-90

041269

API NUMBER 15-163-00414-00-00<sup>na</sup>

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SESW, SEC. 33, T 9 S, R 17 W/EX

330 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Nettie Well # 3-1

Operator: Phillips Pet. Co.

County Rooks 114.36

Name & Address: Route #3 Box 20 A

Well Total Depth 3519 feet

Great Bend, Ks. 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 171 w/cwc

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing License Number \_\_\_\_\_

Address Box 147 Chase, Ks. 67524

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 5 1/2 casing set at 3516 w/ \_\_\_\_\_ sks cement.

Ordered 300 sks 65/35 poz 10% gel w/ 1/4 lb f.c. plus 5 sks hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
4-4-91  
APR 04 1991

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)  
Conservation Division  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00PM Day: 28 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sanded bottom to 3200; spotted 5 sks cement

Shot casing at 800.. Shot pipe at 1400; Pumped down 5 1/2 casing w/300 sks  
cmt w/5 sks hulls in cement. Max 500 lbs. s.i. 300 lbs. Pressured annulus to  
1100 lbs.

Remarks: W.L.M. - 1400.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE APR 05 1991

INV. NO. 31330

*W.L.M.*

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis L. Hamel