

Lease Code # 80-7159
S.M. Wardell

Buyer # B 842637
4-10 15-163-032137-100-00
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 11-30-55
SW NW SEC. 33 T 9 S. R. 17 W/EXX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229
Operator: Phillips Pet. Co.
Name: Route 3, Box 20A
Address: Great Bend, Kansas 67530

2970 feet from S section line
4290 feet from E section line
Lease Name Nettie Well # 1-02
County Rooks 111-89
Well Total Depth 3535 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 203' w/100 sks

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement License Number
Address Hays, Ks.

Company to plug at: Hour: 10:00 Day: 10 Month: April Year: 19 90

Plugging proposal received from Dave Stahl

(company name) Phillips Pet. Co. (phone)

was: 5 1/2" casing set at 3534' w/100 sks: Perf at 3219' - 3428'.

Perf anhy at 1375' and base dakota at ': Casing leaks at 832' and 1064' and sq
w/125 sks cement

Ordered 400 sks 65/35 poz 8% gel w/1/4" f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:20AM Day: 10 Month: April Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing w/350 sks cement plus
5 sks hulls. Max 600#. S.I. 300#.

Pumped in 8 5/8" s.p. w/25 sks cement.
Max 500#. S.I. 200#.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-24-90
INV. NO. 27955
4-10

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

STATE CORPORATION COMMISSION
APR 16 1990
CONSERVATION DIVISION
Wichita, Kansas

(316) 793-842