

041279

8-28-90

API NUMBER 15-163-63493-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CS29ESW, SEC. 33, T 9, S, R 17 W&EXX

330 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Nettie Well # 4-2

Operator: Phillips Pet Co.

County Rooks 114.88

Name & Address Route #3 Box 20 A

Well Total Depth 3535 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 203 circ w/cmt

Abandoned Oil Well x Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number

Address Box 147 Chase, Ks. 67524

Company to plug at: Hour: 12:00 PM Day: 28 Month: August Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 5 1/2 casing set at 3221 w/150 sks cement.

Plug bottom w/sand to 3260 w/5 sks cement on sand. Perf casing at

1400 - 800 and 175. Ordered 300 sks 65/35 poz 10% gel w/1/2 lb f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:00PM Day: 28 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Pumped down 5 1/2 casing w/300 sks cement w/5 sks hulls

mixed in cement: Cement circ up annulus and shut in same. Max 600 lbs.

Shut in 300 lbs.

RECEIVED STATE CORPORATION COMMISSION

APR 04 1991

4-4-91 CONSERVATION DIVISION Wichita, Kansas

Remarks: If additional description is necessary, use BACK of this form.

INVOICED

DATE APR 05 1991

INV. NO. 31328

Signed Dennis L. Hamel (TECHNICIAN)