

4-060673

4-4

2
R

D-23,050

API number: 15-163-20,253-00-01

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW/4 /4 SEC. 33, 09 S, 17 W
3960 feet from S section line
3960 feet from E section line

Operator license# -101

Lease Westhusin OWWO well # 1

Operator: State of Kansas Fee Fund

County Rooks

Address: 2301 E. 13th Street
District #4 - Hays, Ks 67601
Jay Baker

Well total depth 1440 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 209 feet

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: State of Kansas License# -

Address: 2301 E. 13th Street - Hays, Kansas 67601

Company to plug at: Hour: 11:15A.M Day: 4 Month: April Year: 95

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: Order 150 sxs. 60/40 posmix - 8% gel and hulls.
Cedar Hill SWD. Perfs at 1004' - 1024' and 1051' - 1091'. 1SPF

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:40A.M, Day: 4, Month: April, Year: 95

Actual plugging report: 8 5/8" to 209' w/160 sxs. 4 1/2" to 1433'
cemented to surface with 400 sxs. cement. Tied onto production casing
and pumped 150 sxs. cement with 500# hulls. Max. P.S.I. 900#.
S.I.P. 350#. Well plugged according to expected parameters for cement
volume and pressure gradient.

Halliburton Cementing - Randy's Well Service -
Remarks: Leo's Tank Service - Mercury Wireline - Nor-Star - dirt.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES NR NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2111 GL

I did[X] / did not[] observe the plugging.

[Signature]
APR 12 1995
4-12-95
Form CP-2/3
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS