

4-4
3 R
4-060672

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,214-00-00

N2 S2 NW /4 SEC. 33, 09 S, 17 W
3630 feet from S section line
3960 feet from E section line

Operator license# - Lease Westhusin well # 1
Operator: State of Kansas Fee Fund County Rooks

Address: 2301 E. 13th Street Well total depth 3590 feet
District #4 - Hays, Ks 67601 Conductor Pipe: 0 inch @ 0 feet
Jay Baker Surface pipe 8 5/8 Inch @ 159 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: State of Kansas License# -

Address: 2301 E. 13th Street - Hays, Kansas 67601

Company to plug at: Hour: 12:30P.M Day: 4 Month: April Year: 95

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: Order 250 sxs. 60/40 posmix - 10% gel and hulls.
Plug through tubing.


Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:45P.M., Day: 4, Month: April, Year: 95

Actual plugging report: 8 5/8" to 159' w/110 sxs. 4 1/2" to 3589'
with 200 sxs. cement. Perfs from 3444' - 3470'. WLTD at 3392'. Perfs
sanded off from breakin. Perforated at 900' - 1400' - 1880'. Ran tubing
to 3000'+. Pumped 80 sxs. cement with 100# hulls. Pulled tubing to
1500'. Circulated to surface with 75 sxs. cement with 200# hulls. Pulled
tubing. Tied onto annulus and pumped 50 sxs. with 50# hulls. Max. P.S.I.
700#. S.I.P. 250#. Tied onto production casing and pumped 45 sxs. cement
with 150# hulls. Max. P.S.I. 2000#. S.I.P. 1500#. Well plugged according
to expected parameters for cement volume and went well for pressure gradient.

Remarks: Leo's Tank Service - Mercury Wireline - Nor-Star - dirt.
Halliburton Cementing - Randy's Well Service
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 2111 GL

I did[X] / did not[] observe the plugging.


DA
(agent)