

To: 6 041146 X
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-9 15-163-03824-00-01-85-
API NUMBER 15- D-3373 R
SW SW SE, SEC. 34, T 9 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229
Operator: Phillipps Pet Co.
Name & Address: 701 East 10th
Route 3 Box 20A
Great Bend, Kansas 67530

330 feet from S section line
2310 feet from E section line
Lease Name Nettie Well # 002 DOZ
County _____ Rooks 131.59
Well Total Depth 4049 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 168' w/100 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ x D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement License Number _____
Address Hays, Ks.

Company to plug at: Hour: 8:00AM Day: 9 Month: Mar Year: 19 90

Plugging proposal received from Slim Wordell
(company name) P.P. Co. (phone) _____

were: 5 1/2" set at 3462' w/100 sks: 4 1/2" at 3434' to 3550' w/125 sks:
Open hole 3550' - 4049': L.K.C. perfs sq at 3193' - 3417' w/650 sks:
Sq at 1300' and 865' and dakota w/565 sks cement. Cement cir.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30PM Day: 9 Month: Mar Year: 19 90

ACTUAL PLUGGING REPORT R.I.H. w/tubing to 1400'; Pumped 50 sks cement
followed w/225 sks cement through tubing: pulled up to 1150'. Pumped add 120 sks cement
w/hulls in cement. Circ cement surface. Pulled tubing. Pumped add 130 sks cement; Max 500#
s.i. 250#. Pressured up 8 5/8" s.p. 1000#.

Remarks: RECEIVED
If additional description is necessary, use BACK of this form.)

INVOICED 28 1990
did not observe this plugging.

DATE 3-26-80
INV. NO. 22716
3-9

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel