

15-163-19307-00-5-14

D-2453

To: 6 041282
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

Drilled 7-10-50

SE SE SW, SEC. 11, T 9 S, R 19 W&Ex

330 feet from S section line

2970 feet from E section line

Lease Name Chandler Well # SWD D01

County Rooks 127.01

Well Total Depth 3908 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 224 cwc

Abandoned Oil Well Gas Well Input Well SWD Well x D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hays, Ks

Company to plug at: Hour: 9:00AM Day: 14 Month: Mar Year: 19 91

Plugging proposal received from Dave Stahl

(company name) Phillips Pet. Co. (phone)

were: 7" casing set at 3624 w/1400 sks cement: O.H. to 3624 -3908;

Ordered 100 sks common w/1/4 lb f.c. plus ordered 475 sks 65/35 poz 10% gel w/1/4 lb f.c.

plus 5 sks hulls.

Plugging Proposal Received by Dennis Hamel

(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:00AM Day: 14 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Pumped in 7" casing w/100 sks cement w/ 1/4 lb f.c. plus 475 sks cement and 5 sks hulls mixed in cement.

RECEIVED
STATE CORPORATION COMMISSION

4/12/91
APR 12 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks:

INVOICED

If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 4-12-91

INV. NO. 31552

3-14

MAY 03 1991

Signed

Dennis L. Hamel

(TECHNICIAN)

Dennis Hamel