

4-032331

15-163-00152-00-01

11-19

(15-163-00152)

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1-12-80 OWWO

NW NW NE /4 SEC. 04 , 09 , 19 W
4950 feet from S section line
2310 feet from E section line

Operator license# 100

Lease: McClellan "A" OWWO Well # 1

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990044-001

County: Rooks 112.10

Well total depth 3449 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 150 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Chito's Well Service License# 32028

Address: Plainville, Kansas 67663

Company to plug at: Hour: A.M. Day: 19 Month: November Year: 1998

Plugging proposal received from: Kansas Corporation Commission- Dist. #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order work string of 2" tubing.

RECEIVED
12/1/98
10:15 AM
STATE CORPORATION COMMISSION
Wichita, Kansas
CONSERVATION DIVISION

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:45 A.M., Day: 19 Month: November Year: 1998

Actual plugging report: 8 5/8" set at 150' cwc. 5 1/2" set at 3442'.
Prod. Perfs 3181' - 3391'. Cemented through perfs at 883' to surface with 230 sxs cement.
Alt II compliance. Ran in 2000' of 2" tubing - mixed and pumped to circulate 160 sxs cement
blend with 500# hulls. Lay down tubing. Topped off with 25 sxs cement blend. Used 185 sxs
cement blend total. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD
Bottom plug(in place): YES, CALC, NO Anhy. plug: YES X NO
Plugged through TUBING, CASING. Dakota plug: YES X, NO
Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

00