

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 071-20832-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 9-7-2005.

Well Operator: Horseshoe Operating, Inc. KCC License #: 4894
(Owner / Company Name) (Operator's)

Address: 110 W. Louisiana, Ste. 200 City: Midland

State: Texas Zip Code: 79701 Contact Phone: (432) 683 - 1448

Lease: Fertig Well #: 2-35 Sec. 35 Twp. 19 S. R. 40 East West

- C - NW - SE Spot Location / QQQQ County: Greeley

1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 266' Cemented with: 175 Sacks

Production Casing Size: 4-1/2" Set at: 2883' Cemented with: 625 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2850' -63'

Elevation: 3572 (G.L. / K.B.) T.D.: 2883 PBTD: 2882 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per 82-3-114. 190 sxs 60/40 Poz mix, 4% gel, 6 sxs hulls. Pump hulls w/cement to plug bottom. Pump 60/40 Poz w/4% gel to fill pipe. Pressure to 1000#. Hook up to back side and pump 60/40 Poz w/4% gel Pressure to 500#. 4-1/2" & 8-5/8" full top to bottom.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Logs sent in w/ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dave Olson

Phone: (620) 376 - 8190

Address: 110 W. Louisiana, Ste. 200 City / State: Midland, Tx 79701

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: n/a
(Company Name) (Contractor's)

Address: P. O. Box 31 Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-16-07 Authorized Operator / Agent: *Shirley J. Baum*
(Signature)

RECEIVED
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

OCT 18 2007

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HORSESHOE OPERATING, INC.
110 W LOUISIANA STE 200
MIDLAND, TX 79701-3414

October 24, 2007

Re: FERTIG #2-35
API 15-071-20832-00-00
35-19S-40W, 1980 FSL 1980 FEL
GREELEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after April 21, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888