

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 113-00305-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 2/12/54.

Well Operator: WILTON PETROLEUM KCC License #: 7775
(Owner / Company Name) (Operator's)
Address: BOX 391 City: CANTON
State: KS Zip Code: 67428-0391 Contact Phone: (620) 628 - 4466
Lease: MYERS Well #: 1 Sec. 19 Twp. 19 S. R. 5 East West
SW SW SE Spot Location / QQQQ County: RICE

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8 Set at: 186 Cemented with: 125 Sacks
Production Casing Size: 5 1/2 Set at: 3490 Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3420-30 MISS
Sand at 3370 + 5SKS cement pipe recovery 1270
Elevation: 1639 (G.L. / K.B.) T.D.: 3944 PBTD: 3490 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS KCC REQUIRES
800 35SKS 430 35SKS 250 cir. 100SKS


Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NOT AVAILABLE TO US

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: BERNIE RUNDSTROM
Phone: (620) 628 - 4466
Address: BOX 391 City / State: CANTON KS 67428-0391
Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925
(Company Name) (Contractor's)
Address: 401 W MAIN LYONS KS 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): ASAP 10/5/07 - 10:00AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 12/6/06 Authorized Operator / Agent:  (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

** Well already plugged - KCC-Dlg*

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 19 2007
CONSERVATION DIVISION
WICHITA, KS

Dist 02

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
10/15/2007	912

Bill To
Wilton Petroleum Inc. Box 391 Canton, KS 67428

P.O. No.	Terms	Lease Name
	net	Myers 1

Description	Qty	Rate	Amount
Rig Time	18	175.00	3,150.00T
Floor Rental		125.00	125.00T
Sand		35.00	35.00T
Cement	5	9.00	45.00T
Shots	1	160.00	160.00T
Torch		75.00	75.00T
Bored Collar		50.00	50.00T
Welding		75.00	75.00T
Water Truck	6.5	75.00	487.50T
Backhoe	3.5	75.00	262.50T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
10-4-07 Drove to location, raised pole, checked hole, sanded off bottom, loaded hole with water, dug cellar, had to cut ring out of head, unpacked head, set floor, checked hole, sand was at 3370' and bailed 5 sacks cement with bailer, casing parted while pulling slips, had to cut casing head apart to get back to good pipe, welded slips collar on 5 1/2", ripped casing at 1270', left casing on tension, drove home.			
10-5-07 Drove to location, worked pipe free, pulled casing up to 800', pumped 35 sacks, pulled to 430', pumped 35 sacks, pulled to 250', circulated with 100 sacks to surface, pulled rest of casing, tore down floor and rig, emptied pit, cleaned up location.			
Subtotal			\$4,520.00
Sales Tax (6.8%)			\$307.36
Total			\$4,827.36

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 19 2007
CONSERVATION DIVISION
WICHITA, KS