

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21388-00-00
Spot: SESWSE Sec/Twnshp/Rge: 8-26S-5E
599 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BOYER A Well #: 24
County: BUTLER Total Vertical Depth: 2450 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2445		250 SX
SURF	8.625	252		200 SX

\$ 79.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/06/2007 12:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/06/2007 4:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2300', UNITED CEMENTING MIXED & PUMPED 35 SXS CLASS A 3% CC. WAITED 2 HOURS. TAGGED CEMENT @ 1873'. RH SET CIBP @ 500', RAN BOND LOG, SHOWING CEMENT ON SURFACE. RIH W/TBG @ 310', UNITED CEMENTING MIXED & PUMPED 56 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1645 PM 09/06/2007. UNITED CEMENTING TICKET #8013.

Perfs:

Top	Bot	Thru	Comments
2445	2450		
2416	2435		
980	1000		
544	575		

INVOICED
DATE 9/27/07
INV. NO. 2008060498

Remarks: -096.90416.37.79713

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

SEP 26 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

PW