

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20311-00-00

Spot: SENESEW

Sec/Twnshp/Rge: 1-5S-22W

1650 feet from S Section Line,

2970 feet from E Section Line

Lease Name: BAUGUESS A

Well #: 2 3499

County: NORTON

Total Vertical Depth: 3E+0 feet

Operator License No.: 7076 •

Op Name: BLACK DIAMOND OIL, INC.

Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3499	0	200 SX CMT
SURF	8.625	243	0	155 SX CMT

\$ 113.72

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/14/2007 2:30 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: KENNETH VEHIGE

Company: BLACK DIAMOND OIL, INC.

Phone: (785) 623-2035

Proposed Plug Method: Ordered 230 sxs 60/40 pozmix - 4% gel - 600# hulls - 9 sxs gel.  
Plug through casing.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/14/2007 4:00 PM

KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

8 5/8" surface casing set at 243' w/155 sxs cement.  
4 1/2" production casing set at 3499' w/200 sxs cement.  
Perforated production casing at 950' and 1700'.  
Connected to 4 1/2" production casing - pumped 40 sxs cement with 600# hulls - 9 sxs gel - and 140 sxs cement.  
Max. P.S.I. 1200#. S.I.P. 300#.  
Connected to 8 5/8" surface casing - pumped 50 sxs cement.  
Max. P.S.I. 250#. S.I.P. 100#.

**Perfs:**

Top	Bot	Thru	Comments
3469	3472		
3394	3396		
3362	3364		
3314	3316		
3246	3252		

**INVOICED**  
DATE 9/26/07  
INV. NO. 2008 0604 71

Remarks: ALLIED CEMENTING COMPANY-TICKET #25426.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

SEP 24 2007

CONSERVATION DIVISION  
WICHITA, KS

SEP 17 2007

HUNT OIL & GAS COMPANY  
OF KANSAS, INC.

BOX 1196

HAYS, KS 67601

CONTR BIG SPRINGS DRLG., INC.

#2 "A" BAUGUESS

CTY NORTON

1-5-22W  
SE NE SW

GEOL \_\_\_\_\_

FIELD DENSMORE

ELV NA <sup>E</sup> SPD 10/1/83 CARD ISSUED

3/22/84

IP P 25 BOPD

LKC - INTV NA

API 15-137-20,311

Tops ..... Depth/Datum

NO TOPS AVAILABLE

E-RTD ..... 3600

E 8 5/8 " 250; PROD CSG NA  
MCT - CO, PF (LKC) INTV NA, SWB DWN, SO, POP, P 25 BOPD  
- TIGHT HOLE - NO OTHER INFO TO BE RELEASED AT PRESENT -  
WILL RELEASE INFO WHEN AVAILABLE - TEMP COMP - 3/22/84

COPYRIGHT 1983  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS