

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29618-00-00
Spot: SWSESE Sec/Twnshp/Rge: 28-25S-18E
590 feet from S Section Line, 725 feet from E Section Line
Lease Name: HERDER Well #: 1-07
County: ALLEN Total Vertical Depth: 875 feet

Operator License No.: 32642
Op Name: BROWN, NICHOLAS L.
Address: 2481 110TH ST.
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	21	0	

\$ 35.00

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/17/2007 2:30 PM
Plug Co. License No.: 32642 Plug Co. Name: BROWN, NICHOLAS L.
Proposal Rcvd. from: NICK BROWN Company: BROWN, NICHOLAS L. Phone: (620) 496-6242

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 875. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2007 12:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE WELL TO 860'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO 860'. THE PIPE WAS PULLED TO 500' AND 10 SACKS OF CEMENT WERER PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFCE CASING AT SURFACE. ALL 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

SEP 19 2007 CPT

CHANUTE, KS

INVOICED
DATE 9/26/07
INV. NO. 2008060472

Remarks: THE LOCATION OF THIS WELL WAS GPS'D AS HUR 1-07.

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/9

SEP 24 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]