

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-27276-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 34-30S-16E
1420 feet from N Section Line, 1610 feet from E Section Line
Lease Name: HARE Well #: D4
County: WILSON Total Vertical Depth: 898 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String Size Depth (ft) Pulled (ft) Comments
SURF 8.625 20

\$35.00

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/28/2007 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JIM STEGMAN Company: COLT ENERGY, INC Phone: (620) 365-3111

Proposed Plugging Method: Run cement string to TD and plug from btm to top with portland cement and gel spacers.

Plugging Proposal Received By: ALAN DUNNING WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/28/2007 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The 2.875" drill pipe was used as cement string. The drill pipe was lowered to 890' and 20 sacks of cement pumped. The drill pipe was raised to 700' and 10 sacks of cement pumped. The drill pipe was raised to 250' and 60 sacks of cement pumped to bring cement to surface. Gel spacers were used between cement plugs. A total of 90 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
KCC DISTRICT #3
SEP 14 2007
CHANUTE, KS

9/14/07 AMD

INVOICED
DATE 9/26/07
INV. NO. 2008060474

Remarks:

Plugged through: OH

District: 03

Signed Alan M. Dunning
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 24 2007
CONSERVATION DIVISION
WICHITA KS