

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-27230-00-00
Spot: NWNESW Sec/Twnshp/Rge: 19-26S-17E
2465 feet from S Section Line, 3560 feet from E Section Line
Lease Name: JACKSON Well #: 8-07 ACJ
County: WOODSON Total Vertical Depth: 1107 feet

Operator License No.: 30638
Op Name: GREER, JOE V. DBA LITTLE JOE'S OIL
Address: PO BOX 162
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	21	0	

35.98

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/17/2007 1:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: JOE GREER Company: LITTLE JOE'S OIL CO. Phone: (620) 496-7389

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 1107'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND A CONTINUOUS CEMENT PLUG FROM 275' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: PARTIAL
Date/Time Plugging Completed: 09/17/2007 1:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE WELL TOT.D.. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO T.D.. THE 1" PIPE WAS PULLED TO 500' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 275' AND CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. ALL 1" WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

SEP 19 2007

CPT

CHANUTE, KS

INVOICED

DATE 9/26/07
INV. NO. 2008060476

Remarks: THIS WELLS LOCATION WAS GPS'ED AS GPS NO. JAC-07.

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form 301

SEP 24 2007

CONSERVATION DIVISION
WICHITA, KS

CPT