

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-27160-00-00

Spot: SENESE

Sec/Twnshp/Rge: 34-26S-16E

1950 feet from S Section Line,

165 feet from E Section Line

Lease Name: SHOCKLEY-SIZEMORE

Well #: 4

County: WOODSON

Total Vertical Depth: 886 feet

Operator License No.: 33718

Op Name: MEARS, JOHN C.

Address: 4100 240TH ROAD
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	44	0	

\$ 35.00

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/03/2007 8:00 AM

Plug Co. License No.: 31729

Plug Co. Name: OWENS, KEITH DBA OWENS OIL

Proposal Rcvd. from: JOHN MEARS

Company: JOHN MEARS

Phone: (620) 431-2129

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 886'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 300' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 08/03/2007 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

TUBING WAS RAN TO 850'. 10 SACKS OF CEMENT WRER PUMPED THROUGH THE TUBING TO 850'. THE TUBING WAS PULLED TO 500' AND 10 SACKS OF CEMENT WRER PUMPED TO THAT DEPTH. THE TUBING WAS PULLED TO 300'. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE SURFCE CASING AT SURFACE. ALL TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 55 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

SEP 19 2007 CPT

CHANUTE, KS

INVOICED

DATE 9/26/07

INV. NO. 2008060477

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 24 2007

CONSERVATION DIVISION
WICHITA, KS