

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19300-00-01
Spot: SESWSE Sec/Twnshp/Rge: 2-9S-19W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BARRY LKC UNIT Well #: 6-20
County: ROOKS Total Vertical Depth: 3448 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 100 GLENBOROUGH, SUITE 100
HOUSTON, TX 77067

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3440	0	w/200 sxs cmt
SURF	10.75	211	0	w/150 sxs cmt

\$ 112.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2007 8:30 AM
Plug Co. License No.: 32169 Plug Co. Name: DOPITA, DON DBA MAVERICK OIL CO.
Proposal Rcvd. from: JERRY WIRTZ Company: NOBLE ENERGY, INC. Phone: (281) 872-3100

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 800# hulls.
CIBP at 3110' and one at 3430'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2007 3:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RTI to 3400' - pumped 100 sxs cement with 500# hulls.
Pulled tubing to 1968' - pumped 100 sxs cement.
Pulled tubing to 747' - pumped 100 sxs cement with 300# hulls.
Pulled tubing out - let set for one hour - tried to top off with 50 sxs cement - still not full - stopped.
Tied on the backside - pumped 50 sxs cement. S.I.P. 100#.
09/17/2007 - Topped off with 10 sxs cement - full - completed 09/17/2007 - 3:45pm.

Perfs:

Top	Bot	Thru	Comments
3382	3398		
3364	3386		
3344	3360		

INVOICED

DATE 9/26/07
INV. NO. 2008060479

Remarks: ALLIED CEMENTING COMPANY-TICKET #25750.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 24 2007

CONSERVATION DIVISION
WICHITA, KS

SEP 19 2007

Barry A 10
CONTINENTAL OIL #10 BARRY

2-9-19W
SE SW SE

Contr. API 15-163-19300-00-01 ROOKS County

E. 2017 Comm. _____ Comp. 11-18-55 IP 225 BOPD

Tops	Depth	Datum
HEEB	3153	-1136
LANS	3191	-1174
ARB	3439	-1422
TD	3445	-1428

Casing

O. W. W. O.
COMPLETED AS D & A ,
12-7-51

NEW: SQZ & CO 3445: 950'
01H/1 HR, 2160' 01H
/10 HR: PMP 75-B0/8
HR

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

