

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-20446-00-00
Spot: SWNW Sec/Twnshp/Rge: 2-22S-13E
2920 feet from S Section Line, 4290 feet from E Section Line
Lease Name: TODD Well #: 2-B
County: COFFEY Total Vertical Depth: 2405 feet

Operator License No.: 33247 •
Op Name: PETROL OIL & GAS, INC.
Address: PO BOX 34
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2409	0	35 SX
SURF	7	61	0	35SX

\$ 78.16

Well Type: SWD UIC Docket No: D17880.0 Date/Time to Plug: 09/12/2007 7:00 AM
Plug Co. License No.: 31280 Plug Co. Name: BIRK, BRIAN L. DBA BIRK PETROLEUM
Proposal Rcvd. from: BIRK PETROLEUM Company: Phone: (620) 364-1311

Proposed
Plugging
Method:

SEE ATTACHED. 50' cement plug @ 2097' 50' cement plug @ 750' 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/12/2007 6:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

perf. Casing @ 750' & 250', ran tubing to 2097', pumped 20 sxs cement @ 2097', pulled tubing to 750' pumped 20 sxs cement, pulled tubing to 250' pumped 55 sxs cement to surface, pumped gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2360	2375		
2331	2351		
2289	2311		
2269	2286		
2260	2265		

RECEIVED
KCC DISTRICT #3

SEP 17 2007 MH

CHANUTE, KS

INVOICED
DATE 9/26/07
INV. NO. 2008060480

Remarks:

Plugged through: TBG

District: 03

Signed Michael Heffern
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-23

SEP 24 2007

CONSERVATION DIVISION
WICHITA, KS

PH

FED ID# 48-1214033
 MC ID # 165290
 Shop.# 620 437-2661
 Cellular # 620 437-7582
 Office # 316 685-5908
 Office Fax # 316-685-5926
 Shop Address: 3613A Y Road
 Madison, KS 66860

Hurricane Services, Inc.
 P.O. Box 782228
 Wichita, KS 67278-2228

Cement, Acid or Tools
 Service Ticket
 02055

DATE 9-12-07

COUNTY Coffey CITY _____

CHARGE TO Petrol Oil & Gas, Tax

ADDRESS P.O. Box 447 CITY Waverly ST Ks ZIP 66871-0447

LEASE & WELL NO. Todd #2-B CONTRACTOR Hurricane Well Serv

KIND OF JOB Plug To Abandon SEC. _____ TWP. _____ RNG. _____

DIR. TO LOC. _____ (OLD) NEW

Quantity	MATERIAL USED	Serv. Charge	
			600.00
	Pump Truck charge - 7 Hrs. Washing Tubing to bottom (8:00 To 3:00)		650.00
95 SKS	60/40 Premix cement		755.25
325 lbs	Gel 4%		58.50
500 lbs	Gel < Spacers between Plugs		90.00
	BULK CHARGE		
	BULK TRK. MILES < Minimum charge		200.00
15	PUMP TRK. MILES		41.25
	PLUGS		
		5.3% SALES TAX	47.90
		TOTAL	2442.90

T.D. Arbuckle < 2270"

CSG. SET AT _____ VOLUME _____

SIZE HOLE ?

TBG SET AT _____ VOLUME _____

MAX. PRESS. _____

SIZE PIPE 4 1/2"

PLUG DEPTH 2097', 750', 250' to Surface

PKER DEPTH _____

PLUG USED _____

TIME FINISHED 6:00 p.m.

REMARKS: Rig up to 2 3/8" Tubing set @ 720', washed Tubing down to 2097' < Pumped 550 Bbl water >
3:00 p.m. ordered to Plug well by KCC - District 3 Representative. 4 1/2" casing Perf @ 750' & 250'
Spot 20 sks Plug at 2097'
20 sks Plug at 750' } Note: Set Gel Spacers between Plugs
55 sks Plug at 250' to Surface < inside & outside of 4 1/2" casing > "Thank You"

EQUIPMENT USED

NAME Dan Kimberlin UNIT NO. #185
Brad Butke
 HSI REP.

NAME J. Barr UNIT NO. #91
 KANSAS CORPORATION COMMISSION
 witnessed by Company Rep - SEP 24 2007
 OWNER'S REP. CONSERVATION DIVISION
 WICHITA, KS