

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20542-00-01
Spot: N2N2NW Sec/Twnshp/Rge: 20-6S-26W
4950 feet from S Section Line, 3960 feet from E Section Line
Lease Name: HARDESTY Well #: 1
County: SHERIDAN Total Vertical Depth: 3985 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3980	0	w/175 sxs cmt
SURF	8.625	360	0	w/250 sxs cmt

\$ 129.51

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2007 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: PETE FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 600# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2007 12:40 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 360' w/250 sxs cement.
4 1/2" production casing set at 3980' w/175 sxs cement.
PBTB 3919'. Junk in hole. Top of fish at 2353'.
Production casing had holes. Perforated 4 1/2" casing at 420' - 1500' - 2245'.
Ran tubing to 2300' - pumped 200 sxs cement with 600# hulls.
Pulled tubing to 1150' - pumped 100 sxs cement with 150# hulls - cement to surface.
Pulled tubing to surface. Connected to 4 1/2" production casing - pumped 5 sxs cement.
Max. P.S.I 500#. S.I.P. 0#.
Connected to 8 5/8" surface pipe - pumped 65 sxs cement.
Max. P.S.I. 250#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3907	3911		
3890	3893		
3858	3863		
3779	3781		
3768	3772		
3722	3725		

INVOICED
DATE 9/26/07
INV. NO. 2008060483

Remarks: ALLIED CEMENTING COMPANY-TICKET #28742.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

replacement card

RITCHIE EXPLORATION
WICHITA KS 67202

20-06S-26W
C N/2 N/2 NW

1 HARDESTY OWWO

site: 1-3/4 N & 3 W OF LUCERINE KS

city: SHERIDAN

API 15-179-20542

contr: UNKNOWN

field: HORTONVILLE

well:

tr date	spd date	drfg comp	card issued	last revised
07/03/95	06/27/94	06/27/94	07/03/95	08/12/96

ELV: 2659 KB LOG

tops.....	depth/datum
ANH.....	2251 + 408
B/ANH.....	2282 + 377
TOP.....	3496 - 837
HEEB.....	3700 - 1041
TOR.....	3723 - 1064
LANS.....	3738 - 1079
PBTD.....	3936 - 1277
BKC.....	3940 - 1281
LTD OLD.....	3958 - 1299
RTD OLD.....	3985 - 1326

IP status:
OIL, P 7 BO & 40 BWP, SHAW 3723-3728, LKC
3768-3911 OA, (NEW PAY), 06/30/94
INFO RELEASED: 8/12/96 - WAS OIL WELL - TIGHT
HOLE
OLD INFO: OPERATOR WAS A SCOTT RITCHIE, 1
HARDESTY, SPD 10/22/79, 11/01/79 8-5/8" 360 / 250 SX,
4-1/2" 3980 / 175 SX, OIL, P 80 BOPD, LKC 3806-3911 OA,
01/17/80 (CARD ISSUED 01/24/80)
CONTR: MURFIN DRILLING
NO CORES

COPYRIGHT 1996
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

RITCHIE EXPLORATION
WICHITA KS 67202

20-06S-26W
C N/2 N/2 NW

1 HARDESTY OWWO

DST (1) 3756-3781 (LANS), / 30-30-30-30, REC 5' M ISIP 312# FSIP 312# IFP 32# FFP 32#
DST (2) 3795-3820 (LANS), MISRUN
DST (3) 3792-3821 (LANS), / 30-30-45-45, 120' GIP, REC 5' CLEAN OIL, 60' SLI MCO, 60' HOCM
ISIP 426# FSIP 436# IFP 32# -32# FFP 53# -53#
DST (4) 3819-3845 (LKC), / 30-30-30-30, 240' GIP, REC 150' CLEAN OIL, 180' HOCM, 180' MW
ISIP 660# FSIP 639# IFP 53# -128# FFP 170# -223#
DST (5) 3844-3910 (LKC), / 30-30-30-30, 240' GIP, REC 125' CLEAN OIL (GR 31), 120' MO, 120'
OCM ISIP 1215# FSIP 1183# IFP 64# -106# FFP 128# -160#
DST (6) 3909-3960 (PENN), / 30-30-45-45, 100' GIP, REC 200' OCM ISIP 1109# FSIP 1098# IFP
43# -53# FFP 85# -85#
MICT - CO, PF (LKC) 3907-3911, 3890-3893, 3858-3863, 3823-3828, 3806-3808, W / 2 SPF, AC 2000
GAL, SWB DWN, TST 40.87 BO/4 HRS, POP, P 80 BOPD, 1/17/80
NEW INFO: FR 07/03/95, REWORKED 06/27/94 DC 06/27/94 MICT - CO, PB 3936 TD, PF (LKC)
3779.5-3781.5, 3768-3772, W / 3 SPF, AC 500 GAL (15% MCA), SO, PF (TOR) 3722.5-3725.5, W / 3
SPF, AC 300 GAL (15% MCA), SO, SET 2-3/8" TBG 3931, NO PKR, POP, P 7 BO & 40 BWP,
6/30/94, COMMINGLED W/OLD PFS (LKC 3806-3911 OA) - (NEW PAY - SHAW OIL)