

2-070619

STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - Plugging Section
 130 S. Market, Room 2078
 Wichita, Kansas 67202

7-3

API NUMBER: 15-159-04587-00-02

NW NW SE, SECTION 5 TOWNSHIP 20 RANGE 10W

OPERATOR LICENSE # 30364 2310 FEET FROM S SECTION LINE
 OPERATOR RESOURCE OPERATIONS INC. 2310 FEET FROM E SECTION LINE

NAME & P.O. BOX 9487
 ADDRESS TULSA, OK 74157

LEASE NAME: STUEDER #1
 COUNTY: RICE
 WELL TOTAL DEPTH: 3334' 108.35
 PIPE: 7" @ 3334'
 SURFACE CASING: 10" @ 140'

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐

RECEIVED
 SWD KANSAS CORPORATION COMMISSION

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: P.O. BOX 209, CHASE, KS 67524

LICENSE: 31529
 CONSERVATION DIVISION
 WICHITA, KS

COMPANY TO PLUG AT: HOUR: 2:00 DAY: 3 MONTH: 7 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING

PHONE: _____

WERE: TUBING TO BOTTOM 50 SACKS AT 2785'

50 SACKS AT 1300'

50 SACKS AT 900'

200 TO 0'

PLUGGING PROPOSAL RECEIVED BY: J.L.

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { ☒ } PART { ☐ } NONE { ☐ }

COMPLETED: HOUR: 6:00 DAY: 3 MONTH: 7 YEAR: 1996

ACTUAL PLUGGING REPORT: PERFORATED CASING AT 1300', 900', AND 200'. RAN TUBING TO
 BOTTOM, PUMPED 50 SACKS OF CEMENT AT 2785'. PULLED TO 1300', PUMPED 50 SACKS.
 PULLED TO 900', PUMPED 50 SACKS. PULLED TO 200', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT #3038

I ☒ DID NOT OBSERVE THIS PLUGGING.

JACK LUTHI

INVOICED

DATE AUG 07 1996

INV. NO. 46191

FORM CP-2/3
 REV. 7/96