

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21862-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 7-17S-25W
2145 feet from S Section Line, 2145 feet from E Section Line
Lease Name: STUTZ E Well #: 1
County: NESS Total Vertical Depth: 4505 feet

Operator License No.: 6009
Op Name: DOUBLE EAGLE EXPLORATION, INC.
Address: 800 W 47TH ST STE 318
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1190		
PROD	4.5	4500	0	WITH 200 SX CMT
SURF	8.625	320		WITH 185 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/07/2006 9:00 AM
Plug Co. License No.: 33645 Plug Co. Name: PLAINS, LLC
Proposal Rcvd. from: JIM ROBINSON Company: DOUBLE EAGLE Phone: (316) 246-0422

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 09/07/2006 12:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PUMP 40 SX CMT WITH 200# HULLS AT 4005'. 1ST PLUG PULLED TUBING TO 1800' & PUMP 40 SX CMT WITH 200# HULLS. 2ND PLUG PULL TUBING TO 1400' & PUMP 15 SX CMT. PULLED TO 1193' & CIRCULATED HOLE CLEAN. SET CIBP @ 1190'. PRESSURED TO 500#. PERFORATED AT 1150'. PUMP 185 SX CMT. PRESSURED TO 750#. SHUT IN AT 400# & HELD. PUMP 48 SX CMT DOWN ANNULUS. PRESSURED TO 600#. SHUT IN. PRESSURE HELD AT 510#.

Perfs:


Top	Bot	Thru	Comments
4498	4504		

INVOICED
DATE 12-11-06
INV. NO. 2007060895

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4039' OF 2 3/8' TUBING. SETTING DEPTH OF TUBING UNKNOWN.

Plugged through: TBG

District: 01



Signed

Steve Durrant

(TECHNICIAN)