

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21433-00-00

Spot: SW

Sec/Twnshp/Rge: 28-32S-16W

1320 feet from S Section Line, 1320 feet from W Section Line

Lease Name: OASIS

Well #: 28-14

County: COMANCHE

Total Vertical Depth: 5162 feet

Operator License No.: 32204

Op Name: REDLAND RESOURCES, INC.

Address: 6001 NW 23RD ST
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4850		
CIBP		4950		
COND	20	65		WITH 10 SX CMT
PROD	4.5	5199	3630	WITH 225 SX CMT
SURF	8.625	508		WITH 400 SX CMT

#107.77

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 10/04/2007 9:00 AM

Plug Co. License No.: 5105

Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: ALAN VRATIL

Company: VRATIL SERVICES

Phone: (620) 886-3563

Proposed Plugging Method: SET CIBP @ 4950 & 4850'. PLUG AT 970' WITH 12 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/04/2007 10:10 AM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET 2 CIBP'S @ 4950' & 4850'. 1ST PLUG AT 982' WITH 100# HULLS - 12 SX GEL - 50 SX CMT. 2ND PLUG AT 538' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. GOOD RETURNS, CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5022	5085		
4896	4906		


INVOICED
DATE 10/16/07
INV. NO. 2008060591

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

District: 01



Signed

Eric MacLaren

CONSERVATION DIVISION
WICHITA, KS
(TECHNICIAN)

OCT 18 2007

PKT