

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23174-00-00
Spot: NESWNE Sec/Twnshp/Rge: 16-31S-14W
1594 feet from N Section Line, 1362 feet from E Section Line
Lease Name: JACOBS Well #: 1-16
County: BARBER Total Vertical Depth: 583 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 1658 COLE BLVD STE 205
LAKEWOOD, CO 80401

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	84		

35.00

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 09/25/2004 9:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: CHRIS GOTTSCHALK Company: SHELBY RESOURCES Phone: (720) 274-4682

Proposed
Plugging
Method:

FILL HOLE WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2007 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

RAT HOLE DIGGERS SET 20" CONDUCTOR PIPE @ 84'. STERLING DRILLING CUTTING 12 1/2" HOLE BELOW CONDUCTOR 20" PIPE LOST CIRCULATION AT 583'. 20" CONDUCTOR PIPE FELL DOWN HOLE 3'. DRILLING RIG ALSO WENT DOWN HOLE 3'. MOVED RIG OFF HOLE TO DRILL REPLACEMENT WELL. MADE LOCATION READY TO PLUG. BROUGHT 20" CONDUCTOR PIPE BACK TO SURFACE. FILLED IN HOLE AROUND PIPE. PLUGGED RAT HOLE AND MOUSE HOLE. RUN IN 2 3/8" TUBING WITH KNOTCHED COLLAR. TAGGED BRIDGE @ 110'. CLEAN OUT HOLE TO 210'. CIRCULATED CMT FROM 210' TO SURFACE WITH 300 SX CMT.


Perfs:

INVOICED
DATE 10/16/07
INV. NO. 2008060593

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

OCT 09 2007
CONSERVATION DIVISION
WICHITA, KS

PRP