

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22454-00-00
Spot: NWNENE Sec/Twnshp/Rge: 3-33S-4W
4759 feet from S Section Line, 991 feet from E Section Line
Lease Name: STEPHENS TRUST Well #: 1
County: SUMNER Total Vertical Depth: 6647 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4519		200 SX CMT
SURF	10.75	319		275 SX CMT

\$ 216.03

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/27/2007 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: _____ Company: CLARKE CORP. Phone: (620) 886-5665

Proposed Plugging Method: PBTD 4461', PERFS 3986'-3994', 4000'-4020'. CIBP 3930' AND 2 SKS CMT, REC PIPE, 35 SKS AT 750', CIRC CMT 370'-'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/27/2007 10:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE CIBP WAS SET AT 3930' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 3400' AND PULLED FROM THE WELLBORE. TUBING WAS RUN TO 744', WHERE 35 SKS OF CMT WAS CIRC TO SURFACE. THE TUBING WAS PULLED TO 372', WHERE CMT WAS CIRCD TO SURFACE WITH 165 SKS OF CMT.

Perfs:

Top	Bot	Thru	Comments
4000	4020		
3986	3994		

INVOICED
DATE 10/16/07
INV. NO. 2008060597

Remarks: ALLIED CMTG #31268 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

PRT

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 09 2007

CONSERVATION DIVISION
WICHITA, KS